Datasheet



ACI

Features

- Interfaces to most particle therapy accelerator types
- Allows accelerator to connect to up to three treatment rooms plus "room 0"
- Suitable for "step and shoot" and continuous scanning beam delivery
- Communications to treatment room dose control systems via fiber optic channels
- Communication to dose control and room servers via Ethernet
- High level of electrical isolation on all signal and communication paths
- Options for current or voltage levels on analog signals
- Beam stop control and monitoring
- Beam control signals can be routed via an interlock unit to provide a fast beam off method
- Compatible with Pyramid ICI Interlock Control Interface
- Display showing key configuration and diagnostic information
- Web-browser interface for remote monitoring

Applications	 Connecting Pyramid treatment nozzle systems to beam production accelerator systems. Generic particle therapy accelerator interfacing. In combination with Pyramid ICI to provide a beam control and interlocking system. 					
PSI System Control	and Diagnostics Pyramid Technical Consultants					

Datasheet

Connections to accelerat	or and beamline control				
Current Command out	Analog beam current command.				
	Configurable as either 0 to +10 VDC or 0 to 20 mA current.				
Enable Out	Digital fiber optic signal to turn beam on and off for dosimetry control.				
	Note: an internal switch setting allows this signal to only pass to the fiber optic transmitter if the Beam Ready input is present.				
	Note: the signal is routed via the Beam Control connectors. It can therefore be interrupted by an external device (Pyramid ICI or equivalent) as part of an interlock response.				
Beam Ready input	Digital fiber optic signal indicating that accelerator system is ready to deliver beam.				
	Note: an internal switch setting allows this signal to be used to gate the Enable Out signal.				
Beam Enabled input	Digital fiber optic signal indicating that accelerator system is enabled to de- liver beam (beam should be present).				
Frequency In	Digital fiber optic signal with frequency representing the beam energy.				
Reserved In	Digital fiber optic signal reserved for future use.				
Monitor Input Q	Analog input 0 to +10 V indicating how much charge remains in a synchro-				
Monitor Input I	Analog input 0 to +10 V indicating the signal from a measurement by the accelerator of its beam current level.				
Room Select Set	Two bit digital control pattern to set active treatment room in ACI. Bidirec- tional opto-coupled inputs, 5 to 24 V into 10k series resistance.				
	Note: an internal switch allows this selection to be made instead by an Ethernet message.				
Room Select Readout	Two bit digital readout pattern (two relay isolated contact pairs) to allow a remote system to validate the ACI room selection.				
Connections to treatment	rooms				
Enable Room 0,1,2,3	Digital fiber optic inputs requesting beam from rooms 0,1,2,3.				
	Only the input from a selected room is routed to the accelerator by the ACI.				
Transmit / Receive Room 0,1,2,3	Digital fiber optic 10 Mb/s communication channel between M40 I/O devices in the ACI to loop controllers in each treatment room.				
	Control signals to the ACI are:				
	Beam current command and room beam stop in/out. Only the beam current command input from the selected room is routed to				
	the accelerator by the ACI. Only the beam stop "open" command from the selected room 1,2 or 3 is routed to the appropriate beam stop connector by the ACI. The "open" command for room 0 is always routed through, irre-				
	spective of the room selection condition.				
	Signals monitored by the ACI and sent via the communication channel are:				
	Beam current readback, compliance voltage of the beam current com- mand (fault detection), synchrotron charge remaining, beamOK state, room beam stop in/out states, room selected flag, hard and soft interlock flag, beam enabled flag, beam energy frequency value.				
	A				
PSI System Controls and	d Diagnostics Pyramid Technical Consultants				

ACI

Datasheet	ACI
Connections to beam sto	ps
Beam Stop Control 0,1,2,3	Output switchable 24 VDC power to actuator solenoids 0,1,2,3. 24 VDC present should drive stop out of beam (fail safe arrangement). Outputs only enabled for a selected room and for room 0. Inputs for remote contact closures indicating beam stop fully in beam or fully out of beam.
Connections to interlock	system
Beam Control Out to Beam Control In	Signals available for routing via an external interlock device where they can be interrupted as required by an interlock condition: Beam enable command digital Current command analog The ACI delivers the room select bits to the external interlock device where they can be used to route room-centric (soft) interlock response. If no external interlock device is used, then the Out and In connectors should be linked instead by a 9-way pin to pin cable. The ACI detects if there is no connection between Out and In.
Connections to supervisi	ng computer
Ethernet	10/100/1000 BaseT TCP/IP Ethernet connection allows control and moni- toring of some digital states. Control: Room select bits 0,1 (alternative to Room Select connector input) Reserved fiber optic output. Monitor: Beam Ready Beam Enabled Beam Enabled Beam Enable inputs from rooms 0,1,2,3 Room selected readback bits 0,1 Beam energy frequency Reserved fiber optic input The ACI supports a web browser interface that allows these signals to be controlled and monitored remotely.
Controls and switches	
Front panel	Four fiber optic communication loop address selection switches for embed- ded M40 devices handling rooms 0,1,2,3.
Internal	SW2 Beam Enable is or is not gated by Beam Ready (Beam OK) SW3 Room select command bits by Room Select connector or Ethernet SW7 Charge remaining readback 0-20 mA or 0-10 V SW8 Beam current readback 0-20 mA or 0-10 V
PSI System Controls and	I Diagnostics Pyramid Technical Consultants

Datasheet

Connections to embedded M40 devices

Connections used

Four connections for rooms N = 0,1,2,3

A						
Analog In 7	None - connected to DGnd					
Analog In 5	Board installed sense					
Analog In 3	Board installed sense					
Analog In 4	Current Readback					
Analog Out 7	None - not connected					
Analog Out 5	None - not connected					
Analog Out 3	None - not connected					
Analog Out 1	Current Command for Room N					
Analog In 8	None - connected to DGnd					
Analog In 6	None - connected to DGnd					
Analog In 4	Current compliance voltage (internal check)					
Analog In 2	Charge remaining					
Digital In 2	Beam ready (OK)					
Digital In 4	Beam stop "in" sense room N					
Digital In 6	Room N selected					
Digital In 8	Hard interlock set (by external interlock device, ICI)					
Digital Out 2	None - not connected					
Digital Out 4	None - not connected					
Digital Out 6	None - not connected					
Analog Out 8	None - not connected					
Analog Out 6	None - not connected					
Analog Out 4	None - not connected					
Analog Out 2	None - not connected					
Shield	Chassis connection					
PSGnd	Power supply ground for M40					
+24 VDC	24 V power for M40 (200 mA fused in ACI)					
Digital In 1	Beam Enabled					
Digital In 3	Beam energy frequency					
Digital In 5	Beam stop "out" sense room N					
Digital In 7	Soft interlock set (by external interlock device, ICI)					
Digital Out 1	Beam stop command room N (set to open beam stop)					
Digital Out 3	None - not connected					
Digital Out 5	None - not connected					
Digital Out 7	None - not connected					
Digital Out 8	None - not connected					
	Analog In 3Analog In 4Analog Out 7Analog Out 3Analog Out 3Analog Out 3Analog Out 3Analog In 4Analog In 8Analog In 4Analog In 4Oigital In 2Digital In 4Digital In 6Digital Out 2Digital Out 4Analog Out 4Analog Out 4Digital Out 4Digital Out 4Digital In 8Digital Out 4Digital Out 4Digital Out 4Digital Out 5Digital In 1Digital In 3Digital In 3Digital In 3Digital In 4Digital In 3Digital In 5Digital Out 1Digital Out 3Digital Out 3Digital Out 5Digital Out 5Digital Out 7					

Other pins connect DGnd

PSI System Controls and Diagnostics



Pyramid Technical Consultants

Datasheet					ACI		
Service diagnostics							
Serial debug port					to BBB card, rear panel. ty 926475-6		
	2	n/c n/c	5 6	TX n/c			
USB	Internal debug p		on BBI	3 card o	or via serial-USB adaptor (DFR0065) on		
Displays							
Alphanumeric display	2 x 16 c	character b	lue OL	ED on	front panel for device status reporting.		
LEDs	Four se es.	ts of four g	green L	EDs sh	owing status of M40 embedded I/O devic-		
		1 Power			-		
		2 Activity 3 Networ			-		
		4 Device					
	In normal operation 1 and 4 should be illuminated.						
Power indicator	Illumina	Illuminated Pyramid logo on front panel when +5 VDC internal voltage rail is present					
Processors and OS							
ACI BeagleBone Card	Perform	ns POST te	ests of	relay fu	A8) 1 GHz with dual PRU, QNX OS. nction, RAM and flash, memory, battery ACI is disabled if POST fails.		
M40 devices	PIC 18	PIC 18LF8722, no OS.					
PSI System Controls a	nd Diagno	stics			Pyramid Technical Consultants		

Operation

Datasheet	ACI					
Power						
Input	24(+/- 2) VDC 1200 mA; fused 1100 mA nominal for main circuit and 200 mA for cooling fan with PTC fuses.					
Output	Isolated +15 V and -15 V, 65 mA supplies available on rear panel connect- or for use with external isolation amplifiers as necessary.					
Front panel connectors	Do not use. Embedded M40 devices are powered by internal connection.					
Case						
Format	19" rackmount 1U by 250 mm deep with rear panel cooling fan. See figures for dimensions.					
Materials	Steel chassis with Al alloy front panel, polycarbonate decals.					
Protection rating	IP43 (protected against solid objects greater than 1mm in size, protected against spraying water)					
Weight	3.5 kg (7.7 lb)					
Environment						
Operating	 10 to 35 C (15 to 25 C recommended), < 70% humidity, non-condensing, shock and short term vibration < 0.2g all axes (1 to 100 Hz). Recommended location is outside radiation area. May be located in a moderate radiation area together with similar electronics, clear of known expected radiation hot spots. Monitor operation during commissioning ar relocate if necessary. 					
Shipping and storage	-10 to 50 C, < 80% humidity, non-condensing, shock and short term vibra- tion < 1g all axes, 1 to 100 Hz.					
PSI System Controls a	nd Diagnostics Pyramid Technical Consultants					

Datasheet					ACI			
Connectors								
Fiber optic digital logic in- puts		Eight receivers, HFBR 2515 ST bayonet connector (dark gray), rear panel, for multimode HCS fiber, 640 nm visible light.						
Fiber optic digital logic out- puts		Two transmitters, HFBR 1515 ST bayonet connector (light gray), read pan- el, for multimode HCS fiber, 640 nm visible light.						
Fiber optic communication channels	for 10	Four HFBR receiver/transmitter pairs, front panel, ST bayonet connectors for 10 Mb/s communications to Pyramid loop controllers. Multimode HCS fiber, 640 nm visible light.						
Current Command	Two B	Two BNC connectors, rear panel, for 0-20 mA and 0-10 V outputs.						
Beam control signals out-	DSub	9 pin female, rear panel						
going (bottom: to ICI)		• • •		Our mant an an an a st				
	1	Beam enable out	6	Current command out				
	2	Connected sense	7	24 VDC fused				
	3	24 VDC fused	8	DGnd				
	4	Room select bit 0 out	9	DGnd				
	5	Room select bit 1 out						
Beam control signals in- coming (top: from ICI)	DSub 9 pin male, rear panel							
	1 Beam enable return		6	Current command return				
	2	DGnd	7	Hard enabled				
	3	Soft enabled	8	n/c				
	4	Room select bit 0 return	9	DGnd				
	5	Room select bit 1 return						
Ethernet	RJ-45	jack, rear panel						
Monitor Input Q	BNC, r	ear panel, 0-20 mA or 0)-10 V	(internal switch selection)				
Monitor Input I	BNC, r	ear panel, 0-20 mA or 0)-10 V	(internal switch selection)				
Room Select	Phoenix 1787030 locking 3.5 mm header 8 position, rear panel. Mating connector Phoenix 1790506 or Phoenix 1790315.							
	1	Room selected bit 0 comm	6	Room select bit 0 opto in				
	2	Room selected bit 0 n/o	7	Room select bit 0 opto in				
	3	Room selected bit 1 comm	8	Room select bit 1 opto in				
	4	Room selected bit 1 n/o	9	Room select bit 1 opto in				
	(Opto inputs are bidirectional)							
PSI System Controls and	d Diago	ostics		Pyramid Technical	Consultante			

Connectors (continued	d)						
Beam Stop Control	Four DSub 9 pin male, rear panel for beam stops N = 0,1,2,3						
	1 Beamstop N switched 24 VDC		6	PSGnd (24 V ref)			
	2	Beam stop N in limit switch	7	PSGnd (24 V ref)			
	3	Beam stop N out limit switch	8	PSGnd (24 V ref)			
	4	n/c	9	n/c			
	5	n/c					
		limit switch should be n/o a PSGnd to indicate limit is r			mit swite		
Iso Power	Lemo El	PG.0B four pin connector, i	rear	panel.			
	1	+15 VDC isolated	3	Isolated Gnd	1		
	2	-15 VDC isolated	4	Opto indication +5V present			
	1	+24 VDC in 24 V rtn					
Ground lug	M4 threa	aded stud.					



