

K3

# LADDER OVERHANG at RAKE (1'-0" Max.)

All nailing and connection schedules other than those defined in this detail are to be determined by the local building code or design professional.

Nail each Ladder to the Rim Rafter with min. (3) 16d box nails.

Nail the Sheathing to each Ladder with (3) 8d box nails.

