


VERTICAL AND HORIZONTAL REINFORCEMENT HAS BEEN EXCLUDED FOR CLARITY



Temporary shuttering

G-Clamp or other supporting method

The height of the formwork is adjusted to suit the required height of the wall

The vertical reinforcement should continue into the area covered by the temporary shuttering, ensuring that adequate cover is provided, having been specified by the Structural Engineer to BS 5628: 2

Where the top of the wall is required to be sloped, the angle of the formwork may be adjusted so that the line of the slope is followed when the concrete is poured

Project 200mm Stepoc - Standard Details		
Title NON-MODULAR WALL HEIGHTS		
Part Number	ST-200-HADJ	Rev
Drawn By TJF	Date 03-12-09	Scale NTS
Approved By	Date	Drawing is supplied by Anderton Concrete Ltd and must not be reproduced or shown to others without prior written consent.



Units 1 & 2, Cosgrove Business Park  
Soot Hill, Anderton  
Northwich  
Cheshire  
CW9 6AA  
Tel: 0333 234 3434  
www.andertonconcrete.co.uk  
Anderton Concrete Ltd. 2019 ©