KEYNOTES ? CONTRACTOR TO REINSTALL PEOPLE COUNTER IN CEILING ABOVE RESTROOM ENTRANCE. CONTRACTOR TO VERIFY EXACT LOCATION WITH HAS/ARCHITECT PRIOR TO INSTALLATION. CONTRACTOR TO PROVIDE USB RECEPTACLE MODEL "USB20A5W" IN RECESSED BOX TO PROVIDE POWER TO FOR CUSTOMER SATISFACTION METER. CONTRACTOR TO VERIFY EXACT LOCATION AND HEIGHT FOR METER PRIOR TO INSTALLATION WITH 3 CONTRACTOR TO PROVIDE 120V POWER TO FAUCET AND SOAP DISPENSER LOCATED ON VANITY IN RESTROOMS. 4 CONTRACTOR TO PROVIDE 208V POWER TO HAND DRYER LOCATED ON VANITY IN RESTROOMS. CONTRACTOR TO PROVIDE 208V POWER TO CEILING MOUNTED HOIST. CONTRACTOR TO VERIFY EXACT LOCATION OF WITH HOIST REPRESENTATIVE PRIOR TO CONTRACTOR TO COORDINATE WITH A/V INSTALLER FOR ALL INSTALLATION REQUIREMENTS FOR NURSE CALL STATION. CONTRACTOR TO CONNECT DEVICE TO NEAREST 120V CIRCUIT FOR POWER. CONTRACTOR TO PROVIDE 120V POWER TO BIOBIDET WASH DRY TOILET. CONTRACTOR TO COORDINATE WITH BIDET REPRESENTATIVE FOR EXACT LOCATION PRIOR TO INSTALLATION. CONTRACTOR SHALL DISCONNECT EXISTING DRINKING FOUNTAIN CHILLER DURING THE DEMOLITION PHASE. CONTRACTOR TO REUSE EXISTING 120V CIRCUIT TO PROVIDE POWER TO NEW DRINKING FOUNTANS TO BE INSTALLED IN SAME LOCATION. CONTRACTOR TO VERIFY ALL POWER REQUIREMENTS WITH PLUMBING CONTRACRTOR PRIOR TO INSTALLATION. CONTRACTOR TO REMOVE EXISTING CIRCUIT AND REPLACE WITH GFCI RATED BREAKER. PROVIDE 120V CONNECTION VIA JUNCTION BOX (HARDWIRE) FOR TOILET SENSOR. TYPÍCAL FOR ALL^Y WHERE SHÓWN. CONTRACTOR TO PROVIDE POWER AND DATA FOR MONITOR TO BE INSTALLED AT ENTRANCE TO MEN/WOMEN'S RESTROOM. CONTRACTOR TO VERIFY EXACT LOCATION

GENERAL NOTES

- ELECTRICAL CONTRACTOR SHALL REFER TO THE ELECTRICAL SPECIFICATIONS FOR ADDITIONAL DESIGN STANDARDS. THE ELECTRICAL SPECIFICATIONS ARE A BINDING PART OF THE CONSTRUCTION DOCUMENTS.
- B. COORDINATE ALL MOUNTING HEIGHTS AND LOCATIONS WITH ARCHITECTURAL ELEVATIONS AND CASEWORK DRAWINGS PRIOR TO ROUGH-IN OF ANY RECEPTACLE OR OUTLET DEVICE. CONTRACTOR SHALL MAKE NECESSARY

MODIFICATIONS TO DEVICES SHOWN TO PREVENT ANY INSTALLATION CONFLICTS.

- C. CONTRACTOR SHALL ROUTE ALL CONDUIT SHOWN TO BE CONCEALED.
- D. ALL WIRE SHALL BE COPPER STRANDED.
- PRIOR TO ROUGH-IN OF ANY OUTLETS, CONTRACTOR SHALL SCHEDULE AND CONDUCT A WALK THROUGH WITH THE OWNER THE VERIFY EXACT LOCATIONS OF POWER AND DATA LOCATIONS. ALL MODIFICATIONS SHALL BE DOCUMENTED PRIOR TO START OF INSTALLATION.
- F. PROVIDE GFCI PROTECTED RECEPTACLES WHERE SHOWN WITHIN 6" OF SINKS OR LAVATORIES.
- S. ALL SPEAKERS SHOWN SHALL TIE INTO EXISTING SOUND SYSTEM FOR THE
- H. TIE ALL NEW FIRE ALARM DEVICES INTO EXISTING F.A.C.P SERVING THE AREA.



AND MOUNTING HEIGHT WITH OWNER/REP PRIOR TO ROUGH-IN.

CONSULTANT

3131 BRIARPARK DR.

HOUSTON, TX 77042

[T] 713 622 1444

[F] 713 968 9333

www.pgal.com

SUITE 200

HAS AVIATION DEPT.

16930 JOHN F. KENNEDY BLVD. HOUSTON TX 77032 [T] 281 233 1757

[F]281 233 1800

ARCHITECT

5353 WEST ALABAMA ST SUITE 205

HOUSTON, TX 77056 T 832 371 6181 F 832 371 6244 www.VoltAirInc.com Texas Firm: #F-14583 Project # 02.18022

REGISTRATION
Copyright © 2019



_	_	HISTORY
Nº.	DATE	DESCRIPTION
	2020.03.20	ISSUE FOR PERMIT
1	2020.03.26	ADDENDUM #1

DEPARTMENT OF AVIATION RECOMMENDED:		HOUSTON AIRPORT SYSTEM DIRECTOR OR DESIGN REPRESENTATIVE	HAS TIP # 19-171 - HOU
	DEPARTMENT OF AVIATION RECOMMENDED:	DEPARTMENT OF AVIATION RECOMMENDED:	DEPARTMENT OF AVIATION RECOMMENDED: HOUSTON AIRPORT SYSTEM DIRECTOR OR DESIGN REPRESENTATIVE

PROJECT NAME

HAS HOUSTON HOBBY AIRPORT

STATUS ISSUE DATE 2020.03.20

7800 AIRPORT BLVD HOUSTON, TEXAS 77061

PROJECT NUMBER

SHEET TITLE
FLOOR PLAN GATES 44-45 POWER

SHEET NUMBER

E3.02