This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright.Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. Stockport Metropolitan Borough Council 100019571 2021

Cut Line A

Cut Line B

Cheadle Lodge

Library

Existing Victorian post to remain

Existing Channel block to remain

Existing lighting column to be relocated (Location subject street lighting design)

Build out kerb line at junction

Build out kerb line at junction

Build out kerb line at junction

Build out kerb line at junction

Existing lighting column to be relocated (Location subject street lighting design)

Library car park to be amended to incorporate 9 No (2.5m x 5m) 90 degree bays

Parallel parking bays 12 No 2m x 6m bays

ASHFIELD ROAD

HITEGATES ROAD

Landscaping

Landscape Works
Area subject to landscape works, scope of works and planting to be agreed with client
Quantity 348m²

Grass Seeding to Verge
Area to be topsoiled and grass seeded
Detail still to be agreed with client
Quantity 40m²

Tree Planting
For Size / Type see landscape drawing D/0290AB/3000/001
Location of trees subject to determined subject to Statutory undertakes plant
Quantity 4 No

KEY

See Standard detail STP/H/07 for information on kerbs and edgings

- New P.C.C Kerbing (100 to 125 KF) Quantity 213m
- New P.C.C Edgings Quantity 25m
- New Conservation Kerbing (100 to 125 KF) Quantity 238m
- New Conservation Edgings Quantity 252m
- Existing Channel block to remain
- Remove Existing Bollards Quantity 10 No
- Existing Lighting Column to be Relocated Quantity 2 No
- Existing signs to be replaced with new Quantity 3 No
- New Morpeth Bollards incorporating 955 cycle roundel Quantity 2 No
- New pole incorporating 957 cycle sign Quantity 2 No
- Existing Victorian Bollard to remain Quantity 1 No

Footway

Footway Resurfacing
Plane Off 90mm to sub base and lay
30mm Surface Course AC6 Dense Surf 100/150
60mm Binder Coursre to CL 1105
Quantity 600m²

Full Footway Construction
30mm Surface Course to CL1105
60mm Binder Course to CL 1105
100mm Type 1 Recycled Sub-Base to CL803
Quantity 275m²

Footway Construction on Carriageway
30mm Surface Course AC6 Dense Surf 100/150
60mm Binder Course AC20 Dense Bin 100/150
Regulating Binder Course
Quantity 210m²

Footway Construction Flexipave
35mm Flexi-pave Surface Course
100mm Recycled MOT Sub base
Quantity 28m²

PCC Flag Paving
400 x 400 x 63mm PCC Paving Flags to Clause 1104
30mm 3.1 Sand / Cement mortar bed or Polymer modified mortar bed
150mm Type 1 Recycled sub base to CL 803
As per Standard Detail STP/H/02
Quantity 16m²

Tactile Crossing

Buff Tactile Paving - as per Standard Detail STP/H/05
Quantity 57m²

Carriageway

Carriageway - Full Construction
40mm Surface Course Asphalt AC 10 close surf 100/150
60mm Binder Course AC 20 dense bin 100/150 rec to BS 5949987
150mm Road Base AC 32 dense base 100/150 des to BS 594987
200mm MOT Type 1 Recycled Sub Base
Quantity - 164m²

Carriageway - Re-profiling-Resurfacing
Plane out 40mm Carriageway surfacing and lay
40mm Surface Course Asphalt AC 10 close surf 100/150
Regulating Base Course
Quantity - 507m²

Carriageway - Table Construction
Plane out 30mm Carriageway surfacing and lay
25mm Surface Course Asphalt AC 10 close surf 100/150
50mm Binder Course AC 20 dense bin 100/150 core. As per Standard Detail STP/H/41
Quantity - 16m²

Carriageway - Resurfacing
Plane out 40mm Carriageway surfacing and lay
40mm Surface Course Asphalt AC 10 close surf 100/150
Quantity - 988m²

Tree / Vegetation Schedule Works

Trees to Remain
No work required
Quantity 4 No

Trees to be Removed
Young trees with 12mm dia trunk removed due to poor condition
Quantity 50m²

Trees to Remain
Remove Dead Wood and crown lift
Quantity 5 No

Remove overhanging vegetation back to footpath edge
Quantity 243m

FOR CONSTRUCTION

Rev.	Drawn	Checked	Date	Revision Details

AMENDMENTS

STOCKPORT METROPOLITAN BOROUGH COUNCIL
HIGHWAYS AND TRANSPORTATION
STOPFORD HOUSE
STOCKPORT SK1 3XE
TEL 0161 474

CAROLINE SIMPSON
DEPUTY CHIEF EXECUTIVE

Job Title

CHEADLE WALKING & CYCLING ASHFIELD ROAD TO ASHFIELD CRESCENT

Drawing Title

DEVELOPED GENERAL ARRANGEMENT

Drawn	Engineer	Checked	Approved
SEB	SEB	SH	BJD
Date 05/01/21	Date 05/01/21	Date 23/06/21	Date 01/07/21
Size A1	Scale 1/200		
Drawing No. C/0290AB/0100/001			Revision