

MARKET/UNDERBANKS SRB AREA

COMPLETED FACELIFTING SCHEMES



Before



After

◀426 Bridge Street Brow

- Repair roof.
- Repair and reinstate rainwater goods and re-route rainwater goods to the front splayed elevation.
- Remove existing windows and replace with timber sliding sash windows.
- Rebuild high level gable brickwork.
- Remove existing decoration to external elevations, repair brickwork and pointing where necessary and redecorate.



Before



After

Bakers Vaults PH, Market Place ▶

- Repairs to main roof where necessary.
- Clean and repoint brickwork where necessary.
- Repair wrought iron railings to ground floor windows.
- Repair windows and doors.
- Reinstatement new or repair existing leaded windows.
- Redecorate where necessary.



Before



After



Before



After

Robinsons Brewery ▶

- Remove inappropriate windows to front elevation and replace with vertical sliding sash windows.
- Remove existing entrance doors and replace with new hardwood entrance doors.



Before



After



Before



After

◀ Harmony, 26 Little Underbank

- Dismantle brickwork to front elevation above ground floor level.
- Rebuild front elevation to the original pattern using existing bricks where possible and pointing with mortar to match the original.
- Repair existing sliding sash windows.
- Remove existing modern shopfront and install new timber shopfront.
- Carry out decorations and sign writing to shopfront.

Stanley Racing, Little Underbank ▶

- Remove inappropriate modern shopfront.
- Install more traditional timber shopfront.
- Redecorate and install new signage.



Before



After



Before



After

◀ 15 Little Underbank

- Remove existing paint from external brickwork and stonework.
- Repoint brickwork / stonework where necessary.
- Reinststate windows to front elevation to original pattern.
- Reinststate front entrance doors to the original design.
- Redecorate woodwork.



Before



After

◀ Turners Vaults, Little Underbank

- Remove existing paint from external brickwork and stonework.
- Repoint brickwork / stonework where necessary.
- Reinstate windows to front elevation to original pattern.
- Reinstate front entrance doors to the original design.
- Redecorate woodwork.



Before



After