This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office © Crown copyright.Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.Stockport Metropolitan Borough Council AC0000804794 2025

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

New pole with Speed limit signs and re-erect TRO sign

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

New pole with Speed limit signs and re-erect TRO sign

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

New pole with Speed limit signs and re-erect Bus Lane and TRO signs

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

New pole with Speed limit signs and re-erect TRO sign

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

Erect New Signs above existing sign with pole extension. Existing pole and sign to be maintained.

Remove existing 30mph Zone ENDS Sign and replace with 20mph Signs

Remove existing 30mph Zone ENDS Signs and replace with 20mph Signs

KEY

- Proposed 20MPH Extents
- Existing 20MPH Zone
- 20 S1 — Dia. 670 Ø600mm 20mph Sign Quantity 29 No.
- 30 S2 — Dia. 670.3 Ø600mm 20mph Sign Quantity 27 No.
- 20 S3 — Dia. 670 Ø300mm 20mph Repeater Sign Quantity 30 No.
- New Pole. 8 No.
- Existing Pole
- Existing Street Lighting Column
- 20 — Dia. 1065 20mph Roundel Road Marking 1.6m Length 13 No.

Note
Refer to Drawing: C/5203-20MPH/1200/002 for Sign Schedule.

All Street Furniture to be set out on site with SMBC Engineer.

SITE SPECIFIC HAZARDS

IT HAS BEEN ASSUMED BY THE DESIGNER THAT THE WORKS ARE UNDERTAKEN BY A COMPETENT CONTRACTOR WHO IS AWARE OF THE RISKS NORMALLY ASSOCIATED WITH THIS TYPE OF WORK.
TAKE NOTE OF THE FOLLOWING:

01 WORKING ADJACENT STATUTORY UNDERTAKERS EQUIPMENT
02 WORKING IN PROXIMITY TO OVERHEAD CABLES/SERVICES
03 BUS TRAFFIC FLOWS
04 BUSY TOWN / DISTRICT CENTER ENVIRONMENT
05 DISABLED/ VISUALLY IMPAIRED PEDESTRIANS
06 ROUTES TO SCHOOL / PROXIMITY TO SCHOOLS
07 PERCEIVED RISK OF ANTISOCIAL BEHAVIOR
08 CONTAMINATED MATERIAL
09 NEEDLE STICK INJURIES
10 INFECTIOUS DISEASES AND PANDEMICS

NOTE NUMBERS FOLLOW THE SEQUENCING IN THE DESIGNERS RISK ASSESSMENT.
REFER TO DOCUMENT REFERENCE: 5203 20MPH DESIGNERS RISK ASSESSMENT.

FOR CONSTRUCTION

STOCKPORT
METROPOLITAN BOROUGH COUNCIL

HIGHWAYS AND TRANSPORTATION
STOPFORD HOUSE
STOCKPORT SK1 3XE
Tel: 0161 474

MARK GLYNN
DIRECTOR OF PLACE MANAGEMENT

Rev.	Drawn	Checked	Date	Revision Details

	DRAWN	ENGINEER	CHECKED	APPROVED	
	SK	SK	SHL	PWC	
	DATE 09/12/25	DATE 09/12/25	DATE 09/12/25	DATE	

SCALE 1500 @ A1

DRAWING NUMBER C/5203-20MPH/0100/001

Revision _

JOB TITLE 5203-20MPH HEATON CHAPEL

DRAWING TITLE GENERAL ARRANGEMENT