CH475-D240125



Naqeeb Ur Rehman JK Williams Pty Ltd 39-53 Jack Williams Drive, Penrith NSW 2750

iwilliam@jkw.com.au

Re: Dust Monitoring April 2024 - Westlink

Dear Sir,

Compliance Health & Environmental Consulting (CHEC) were engaged by JK Williams Pty Ltd to undertake monthly Depositional Dust Monitoring for the site located at 63 Abbotts Road, Kemps Creek, identified as Lot 11 in DP252503.

Six Dust Deposition Gauges (DDG1-DDG6) were initially installed at representative locations along the Site boundary nearest to sensitive receptors, in accordance with the guidelines provided by AS/NZS 3580.1.1:2016. DDG2 and DDG3 were removed at the end of the October 2023 monitoring period as works were completed in this area.

Works commenced in the Stage 2 area to the south of the property in mid-March 2024. As such, DDG6 was moved to the south western boundary, and two more dust gauges were installed along the new southern boundary. Refer to **Figure 1**-Site layout with sample locations. The gauges were constructed in accordance with AS/NZ3580.1.1:2016-Methods for sampling and analysis of ambient air. Method 10.1: Determination of particulate matter-deposited matter-Gravimetric method.

A 150mm diameter glass funnel was placed within a 4L glass collection bottle using a rubber stopper with a drain. Each DDG was then placed within a PVC casing for protection and fixed to a star picket on site. Bird protection was constructed on the PVC pipe to prevent birds perching on the funnel. Gauges were placed 2m above ground level. This dust report details results from the 8th of April to the 6th May 2024.

Dust is assessed as insoluble solids as defined by AS 3580.10.1–1991 (AM-19) and is made up of both combustible and non-combustible materials. The obligation to monitor dust relates to the primary activity, being soil disturbance as a result of earthworks, therefore, the non-combustible and dissolved component (generally recognised as mineral salts) are the primary measurements of concern to determine compliance.

The sampling method does not provide real time data, but provides an estimate of the mean surface concentration of deposited matter settling from the air over a period of one month.

The gauges were analysed at a NATA certified laboratory where the collected sediment was weighed and dried to measure particles in the air, less the combustible matter to give total non-combustible material collected in the deposition gauges. The resultant data represents the potential exposure to dust for those receptors, being local residences.

The depositional dust monitoring criteria are as follows:

- Annual average total deposited dust level is 4g/m²/month.
- Maximum monthly increase in deposited dust level is 2g/m²/month



Table 1 indicates that the highest recorded dust concentration was observed at DDG8, having a total solids concentration of 5.1g/m² that included 1.6g/m² of insoluble solids. The insoluble solids contained 1.3g/m² of combustible solids, and 0.3g/m² of non-combustible solids (mineral dust). Refer to **Attachment 1** – NATA Certified Results.

Table 1 - March Dust Deposition Analysis (g/m²/month)

Gauge	Insoluble	Combustible	Non-Combustible	Soluble	Total
DDG1	1.9	1.7	0.2	1.3	3.2
DDG4	1.2	1.1	0.2	3.2	4.5
DDG5	1	0.8	0.2	2.8	3.8
DDG6	1.6	1.4	0.1	2.5	4
DDG7	0.5	0.4	0.1	3.9	4.4
DDG8	1.6	1.3	0.3	3.5	5.1

Table 2 indicates that no monthly change of insoluble solids or non-combustible solids exceeded the monthly change criteria.

The rolling averages for DDG4 and DDG6 exceeded the criteria of 4 g/m 2 with average concentrations of 5 g/m 2 and 5.8 g/m 2 respectively. The rolling averages for mineral dust remains compliant at all locations.

Table 2 - Monthly Changes and Rolling Averages (g/m²/month)

	Total Dust (AS	3580.10.1-2016)	Non-Combustible Solids				
Gauge	Monthly ∆	Rolling Avg	Monthly ∆	Rolling Avg			
DDG1	1.5	1	0.2	0.8			
DDG4	0.5	4.6	0.2	2.5			
DDG5	0.4	2	0.2	0.6			
DDG6	-0.3	5.3	0.1	2.6			
DGG7	-0.3	0.7	0.1	0.1			
DDG8	1.4	0.9	0.3	0.3			
Criteria	2	4	1				

Whilst dust concentrations generally decreased over the month, it is noted that the average dust concentrations at DDG4 and DDG6 continue to exceed the monthly average criteria. The averages are primarily attributed to significant concentrations reported in October 2023 and have continued to decrease since. It is expected that if compliant concentrations continue to be measured, the rolling average will eventually become compliant.

The prevailing wind for this month was from the north-west as shown on **Figure 2**. The average wind speed for the month was 1.5km/hr with a maximum of 22.5km/h occurring from the east.

If any further information is required regarding this matter, please feel free to contact the undersigned during business hours.

Regards,

Jayden Gross

Environmental Consultant

Compliance Health & Environmental Consulting Pty Ltd



Figure 1 - Site Layout






Dust Deposition Gauge Location


____ Site Area



Dust Deposition Gauge Locations										
Site Address 63 Abbotts Road, Kemps Creek	Project No. CH1475	Figure No.	17/04/2024							
JK Williams Pty Ltd	Scale NTS	Compiled CV	Revision Rev. 1							




April Wind Rose



Wind Speed (km/hr)

38+ 28-38 19-28 11-19 5-11 0-5

Average value: 1.5
Maximum value: 22.5
Prevailing direction: 90



		STODY RECORD ABN 50 005 085 521	Sydney La Unit F3 Bld.I 02 9900 840	boratory F 16 Mars Road Lane Cove West N O EnviroSampleNSW@eurofins.	VSW 2066		tory d Place Murarrie QLi viroSampleQLD@eu			aboratory 1 Leach Highway Kew 9600 EnviroSample				6	Monterey	Laboratory Road Dandenong South \	/IC 3175
Company	CUEC		Project №	1475			ct Manager			5000 Envirosample		Sampler(s)	00	3 8564 500	00 EnviroSampleVic@e	urofins.com
Address			Project Name	Kemps	crest	EDI ESda	D Format t, EQuIS etc				Har	nded over	by				
Contact Name			r *Fillered *, ماري								Ema	il for Invo	oice				
Phone No.			Siy Total o								Ema	il for Res					
			Analyses ed please specie used to attrac								C		Containe ainer type &	e rs size if necess	ary.	Default will be 5	around Time (TAT) 5 days if not ticked.
Special Direction	ns		Analyses fials are requested, please spec TE code must be used to attrace TE code must be used												delines)	Overnight (rep	
Purchase Order			metals are SUITE ∞de								astic	astic astic	ar Glass	Bottle	4, WA Gui	Same day 2 days 5 days (Standa	☐ 1 day ◆
Quote ID №	21042	CHEN	Matrix								500mL Plastic	250mL Plastic 125mL Plastic	200mL Amber Glass 40mL VOA vial	500mL PFAS Bottle	tos AS496	5 days (Standa	ard)
N≘	Client Sample ID	Date/Time 6	Matrix Solid (S) Pater (W)										200	500	Other (Asbestos AS4964, WA Guidelines)	Sample (/ Dangerous Good	Comments ds Hazard Warning
1 pp 2 pp 6 3 pp 6 4 pp 6 5 pp 6 6 pp 6	61	8/4-6/5	X														
2 PPG	74	7							l lis								
3 PPG	5													Lein			MEET
1 PDG	6																
7174°	7																
DPC	78	4	1														
7																	
3																	
																	1811
0																	
		Total Count	s The last														
ethod of Shipmen	Page hard Bu)		Postal Name			Si	gnature				Date				Time	
Eurofins mgt Laboratory Use O		Marse		MEL PER ADL NTL					Date	至6/5/2	1	Time	(58/2	94		26.
rofine Environment T		F. F. 1.3		·	oigni	acure			Date			Time			1	Report №	- 10



Environment Testing

Compliance Health & Environmental Consulting P/L PO Box 275 Gosford NSW 2250





NATA Accredited Accreditation Number 1261 Site Number 18217

Accredited for compliance with ISO/IEC 17025 – Testing NATA is a signatory to the ILAC Mutual Recognition Arrangement for the mutual recognition of the equivalence of testing, medical testing, calibration, inspection, proficiency testing scheme providers and reference materials producers reports and certificates.

Attention: RESULTS - ALL SRAS HERE ONLY - NO INVOICES

Report 1094076-A
Project name KEMPS CREEK

Project ID 1475

Received Date May 06, 2024

Client Sample ID			DDG 1	DDG 4	DDG 5	DDG 6
Sample Matrix			Dust Deposition	Dust Deposition	Dust Deposition	Dust Deposition
Eurofins Sample No.			S24- My0014777	S24- My0014778	S24- My0014779	S24- My0014780
Date Sampled			May 06, 2024	May 06, 2024	May 06, 2024	May 06, 2024
Test/Reference	LOR	Unit				
Dust Deposition						
Combustible Solids	0.1	g/m2.mth	1.7	1.1	0.8	1.4
Soluble Solids	0.1	g/m2.mth	1.3	3.2	2.8	2.5
Total Solids Dried at 103 °C to 105 °C	0.1	g/m2.mth	3.2	4.5	3.8	4.0
Volume (total)*	0.1	mL	750	850	750	700
Ash*	0.1	g/m2.mth	0.2	0.2	0.2	0.1
Insoluble Solids	0.1	g/m2.mth	1.9	1.2	1.0	1.6

Client Sample ID			DDG 7	DDG 8
Sample Matrix			Dust Deposition	Dust Deposition
Eurofins Sample No.			S24- My0014781	S24- My0014782
Date Sampled			May 06, 2024	May 06, 2024
Test/Reference	LOR	Unit		
Dust Deposition				
Combustible Solids	0.1	g/m2.mth	0.4	1.3
Soluble Solids	0.1	g/m2.mth	3.9	3.5
Total Solids Dried at 103 °C to 105 °C	0.1	g/m2.mth	4.4	5.1
Volume (total)*	0.1	mL	800	700
Ash*	0.1	g/m2.mth	0.1	0.3
Insoluble Solids	0.1	g/m2.mth	0.5	1.6



Environment Testing

Sample History

Where samples are submitted/analysed over several days, the last date of extraction is reported.

If the date and time of sampling are not provided, the Laboratory will not be responsible for compromised results should testing be performed outside the recommended holding time.

DescriptionTesting SiteExtractedHolding TimeDust DepositionSydneyMay 06, 20245 Days

- Method: LTM-INO-4160 Determination of Dust Deposition of Ambient Air

Report Number: 1094076-A



Eurofins Environment Testing Australia Pty Ltd

Site# 25403

ABN: 50 005 085 521

Melbourne Geelong Canberra Sydney 6 Monterey Road 19/8 Lewalan Street 179 Magowar Road Unit 1,2 Dacre Street 1/21 Smallwood Place 1/2 Frost Drive Dandenong South Grovedale Girraween Mitchell VIC 3175 VIC 3216 NSW 2145 ACT 2911 +61 2 9900 8400 +61 3 8564 5000 +61 3 8564 5000 +61 2 6113 8091 NATA# 1261 NATA# 1261 NATA# 1261 NATA# 1261

Site# 18217

Site# 25466

Brisbane Newcastle Murarrie Mayfield West QLD 4172 NSW 2304 T: +61 7 3902 4600 +61 2 4968 8448 NATA# 1261 NATA# 1261 Site# 25079 & 25289 Site# 20794

Perth 46-48 Banksia Road Welshpool WA 6106 +61 8 6253 4444 NATA# 2377 Site# 2370

02 4304 0091

ABN: 91 05 0159 898

ABN: 47 009 120 549 Perth ProMicro 46-48 Banksia Road Welshpool WA 6106 +61 8 6253 4444

Auckland 35 O'Rorke Road Penrose, Auckland 1061 +64 9 526 4551 IANZ# 1327

NZBN: 9429046024954

Auckland (Focus) Unit C1/4 Pacific Rise. 43 Detroit Drive Mount Wellington, Auckland 1061 +64 9 525 0568 IANZ# 1308

May 6, 2024 12:20 PM

Christchurch Tauranga Rolleston, Christchurch 7675 Tauranga 3112 +64 3 343 5201 IANZ# 1290

1277 Cameron Road. Gate Pa, +64 9 525 0568 IANZ# 1402

Company Name: Address:

email: EnviroSales@eurofins.com

web: www.eurofins.com.au

Compliance Health & Environmental Consulting P/L

PO Box 275

Gosford NSW 2250

Site# 1254

Project Name:

KEMPS CREEK

Project ID:

1475

Order No.:

Report #: Phone:

Fax:

Dust Deposition

Received: 1094076 Due:

NATA# 2561

Site# 2554

May 13, 2024 **Priority:** 5 Dav

Contact Name: RESULTS - ALL SRAS HERE

Eurofins Analytical Services Manager: Bonnie Pu

Sample Detail

Sydney Laboratory - NATA # 1261 Site # 18217								
External Laboratory								
No Sample ID Sample Date Sampling Matrix LAB ID								
1	DDG 1	May 06, 2024		Water	S24-My0014777	Х		
2	DDG 4	May 06, 2024		Water	S24-My0014778	Х		
3	DDG 5	May 06, 2024		Water	S24-My0014779	Х		
4	DDG 6	May 06, 2024		Water	S24-My0014780	Х		
5	DDG 7	May 06, 2024		Water	S24-My0014781	Х		
6	DDG 8	May 06, 2024		Water	S24-My0014782	Х		
Test	Counts					6		



Internal Quality Control Review and Glossary

General

- 1. Laboratory QC results for Method Blanks, Duplicates, Matrix Spikes, and Laboratory Control Samples follow guidelines delineated in the National Environment Protection (Assessment of Site Contamination) Measure 1999, as amended May 2013. They are included in this QC report where applicable. Additional QC data may be available on request
- 2. Unless otherwise stated, all soil/sediment/solid results are reported on a dry weight basis.
- 3. Unless otherwise stated, all biota/food results are reported on a wet weight basis on the edible portion.
- 4. For CEC results where the sample's origin is unknown or environmentally contaminated, the results should be used advisedly.
- Actual LORs are matrix dependent. Quoted LORs may be raised where sample extracts are diluted due to interferences
- Results are uncorrected for matrix spikes or surrogate recoveries except for PFAS compounds where annotated.
- 7. SVOC analysis on waters is performed on homogenised, unfiltered samples unless noted otherwise.
- 8. Samples were analysed on an 'as received' basis.
- 9. Information identified in this report with blue colour indicates data provided by customers that may have an impact on the results.
- 10. This report replaces any interim results previously issued.

Holding Times

Please refer to the 'Sample Preservation and Container Guide' for holding times (QS3001).

For samples received on the last day of holding time, notification of testing requirements should have been received at least 6 hours before sample receipt deadlines as stated on the SRA

If the Laboratory did not receive the information in the required timeframe, and despite any other integrity issues, suitably qualified results may still be reported.

Holding times apply from the sampling date: therefore, compliance with these may be outside the laboratory's control.

For VOCs containing vinyl chloride, styrene and 2-chloroethyl vinyl ether, the holding time is seven days; however, for all other VOCs, such as BTEX or C6-10 TRH, the holding time is 14 days

Units

mg/kg: milligrams per kilogram mg/L: milligrams per litre ppm: parts per million μg/L: micrograms per litre ppb: parts per billion %: Percentage

org/100 mL: Organisms per 100 millilitres NTU: Nephelometric Turbidity Units MPN/100 mL: Most Probable Number of organisms per 100 millilitres

Colour: Pt-Co Units (CU) CFU: Colony Forming Unit

Terms

APHA American Public Health Association CEC Cation Exchange Capacity COC Chain of Custody

CP Client Parent - QC was performed on samples pertaining to this report CRM Certified Reference Material (ISO17034) - reported as percent recovery.

Dry Where moisture has been determined on a solid sample, the result is expressed on a dry weight basis

Duplicate A second piece of analysis from the same sample and reported in the same units as the result to show comparison.

LOR Limit of Reporting.

LCS Laboratory Control Sample - reported as percent recovery.

Method Blank In the case of solid samples, these are performed on laboratory-certified clean sands and in the case of water samples, these are performed on de-ionised water NCP Non-Client Parent - QC performed on samples not pertaining to this report, QC represents the sequence or batch that client samples were analysed within.

RPD Relative Percent Difference between two Duplicate pieces of analysis SPIKE Addition of the analyte to the sample and reported as percentage recovery

SRA Sample Receipt Advice

The addition of a similar compound to the analyte target is reported as percentage recovery. See below for acceptance criteria Surr - Surrogate

Tributyltin oxide (bis-tributyltin oxide) - individual tributyltin compounds cannot be identified separately in the environment; however, free tributyltin was measured, and its values were converted stoichiometrically into tributyltin oxide for comparison with regulatory limits. TRTO

TCI P Toxicity Characteristic Leaching Procedure TEQ Toxic Equivalency Quotient or Total Equivalence

QSM US Department of Defense Quality Systems Manual Version 6.0

US EPA United States Environmental Protection Agency

WA DWER Sum of PFBA, PFPeA, PFHxA, PFHpA, PFOA, PFBS, PFHxS, PFOS, 6:2 FTSA, 8:2 FTSA

QC - Acceptance Criteria

The acceptance criteria should only be used as a guide and may be different when site-specific Sampling Analysis and Quality Plan (SAQP) have been implemented.

RPD Duplicates: Global RPD Duplicates Acceptance Criteria is ≤30%; however, the following acceptance guidelines are equally applicable:

Results <10 times the LOR: No Limit

Results between 10-20 times the LOR: RPD must lie between 0-50% Results >20 times the LOR: RPD must lie between 0-30%

NOTE: pH duplicates are reported as a range, not as RPD

Surrogate Recoveries: Recoveries must lie between 20-130% for Speciated Phenols & 50-150% for PFAS. SVOCs recoveries 20 - 150%, VOC recoveries 50 - 150%

PFAS field samples containing surrogate recoveries above the QC limit designated in QSM 6.0, where no positive PFAS results have been reported or reviewed, and no data was affected.

QC Data General Comments

- 1. Where a result is reported as less than (<), higher than the nominated LOR, this is due to either matrix interference, extract dilution required due to interferences or contaminant levels within the sample, high moisture content or insufficient sample provided
- 2. Duplicate data shown within this report that states the word "BATCH" is a Batch Duplicate from outside of your sample batch but within the laboratory sample batch at a 1:10 ratio. The Parent and Duplicate data shown are not data from your samples.
- 3. pH and Free Chlorine analysed in the laboratory Analysis on this test must begin within 30 minutes of sampling. Therefore, laboratory analysis is unlikely to be completed within holding time. Analysis will begin as soon as possible after sample receipt.
- 4. Recovery Data (Spikes & Surrogates) where chromatographic interference does not allow the determination of recovery, the term "INT" appears against that analyte.
- 5. For Matrix Spikes and LCS results, a dash "-" in the report means that the specific analyte was not added to the QC sample.
- 6. Duplicate RPDs are calculated from raw analytical data; thus, it is possible to have two sets of data



Environment Testing

Comments

Sample Integrity

 Custody Seals Intact (if used)
 N/A

 Attempt to Chill was evident
 N/A

 Sample correctly preserved
 Yes

 Appropriate sample containers have been used
 Yes

 Sample containers for volatile analysis received with minimal headspace
 Yes

 Samples received within HoldingTime
 Yes

 Some samples have been subcontracted
 No

Authorised by:

Nileshni Goundar Analytical Services Manager Ryan Phillips Senior Analyst-Inorganic

Glenn Jackson Managing Director

Final Report - this report replaces any previously issued Report

- Indicates Not Requested
- * Indicates NATA accreditation does not cover the performance of this service

Measurement uncertainty of test data is available on request or please click here.

Eurofins shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Eurofins be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested. Unless indicated otherwise, the tests were performed on the samples as received.

Report Number: 1094076-A